SHIMLA JAL PRABHDHAN NIGAM LTD.

TEST REPORT

Report No.	LSWW for Shimla city	
Name and address of sender	Koti Bharandi (Been Nala)	
Division	Water distribution division	
Sub-division	Sanjauli	
Name of scheme and location of source	W.T.P. Ashwanikhad	
Date and time of collection	11-10-2024 at 11:00 AM	
Date and time of receipt at laboratory	11-10-2024 at 11:15 AM	
Date and time of commencing	11-10-2024 at 11:30 AM	
Type of sample	Filter water	
Quantity of sample	500 ml	
Date of reporting	11-10-2024	
Testing protocol	IS10500:2012	

A. PHYSICAL TESTS

S.no.	Tests	Acceptable limit	Permissible limit in the absence of	Result of sample
			alternate source	
1.	Temperature (°C)			17.4°C
2.	Turbidity [NTU]	1	5	0.65 NTU
3.	Conductivity (µS)			84.3 μs
4.	Total Dissolved Solids	500	2000	53.5 ppm
	(Mg/L or ppm)			
5.	Color (Hazen)	5	15	Underrange
				(Range:25-1000 Pt/Co(Hz)
6.	Odour	Agreeable	Agreeable	No odour
7.	Taste	Agreeable	Agreeable	Normal

B. CHEMICAL TESTS

S.No.	Tests	Acceptable limit	Permissible limit in the absence of alternate source	Result of sample
1.	pH value	6.5-8.5	No relaxation	8.02
2.	Total Alkalinity (Mg/l)	200	600	30 mg/l
3.	Chlorides (Mg/l)	250	1000	10.342 mg/l
4.	Total Hardness (Mg/l)	200	600	58 mg/l
5.	Residual Chlorine (Mg/I or ppm)	0.2	1.0	2.5 ppm at w.t.p.
6.	Nitrate (Mg/l)	45	No relaxation	Underrange (Range; 0.3-30.0 mg/l)
7.	Iron (Mg/I)	0.1	1.0	0.01 mg/l (Range; 0.01-2.00 mg/l)
8.	Fluoride (Mg/l)	1.0	1.5	0.42 mg/l (Range; 0.08-2.00 mg/l)
9.	Sulphate (Mg/l)	200	400	16.2 mg/l (Range; 1.0-25.0 mg/l)
10.	Manganese (Mg/I)	0.1	0.3	0.02 mg/l (Range; 0.05-6.00 mg/l)

C. BACTERIOLOGICAL TESTS (MPN/100)

Note:- Bacteriological tests are under incubation of 48 hours.

C. BACTERIOLOGICAL TESTS (MPN/100)

- > Date of collection of sample:-09-10-2024
- > Date of commencing:- 09-10-2024
- > Date of Reporting:- 11-10-2024 (after 48 hours of incubation)

After 24-48 hours of incubation, the MPN in 100 ml of water sample:-

Sample	Volumes of sample		MPN for 100 ml
	50 ml	10 ml	
Filter water	0	0	0

 Coli form count should be zero in any sample of 100 ml of water entering the distribution system.

Chemist

Water testing laboratory

Ashwanikhad